ROYALTY CALCULATION

Name of work :- Development of park and Construction of watchmen room at Sidedahalli Govt. School Park in Dasarahalli zone.

Description	Qty in Cum	Constant	Total Qty
Plain Cement Concrete 1:3:6			
Sand	25.03	0.465	11.64
Jelly	25.03	0.892	22.33
Cement Concrete M20			
Sand	35.27	0.43	15.17
Jelly	35.27	0.69	24.34
Precast Concrete Slab 100MM thick			
Sand	0.72	0.46	0.33
Jelly	0.72	0.88	0.63
Size stone masonary			
Size stoney	47.44	1.00	47.44
Sand	47.44	0.45	21.35
100 mm d/s granite boulders			
Jelly	1.32	1.00	1.32
40mm d/s jelly			
Jelly	1.32	1.00	1.32
20 mm nominal size			
Jelly	1.32	1.00	1.32
6 mm nominal size			
Jelly	1.32	1.00	1.32
Sand			
Sand	16.73	1.00	16.73

Sl	Items	Qty	Rate	Amount
1	Sand	48.48	138	6690.24
2	Jelly	52.58	126	6625.08
3	Size	47.44	184	8728.96
			Total	22044.28

Asst.Engineer
Project Division

Asst.Executive Engineer
Project Division

Scanned with CamScanner